

Shelbourne Street Improvements Project

Design Highlights - Phase 1 (McKenzie Ave to Torquay Dr)

- Northbound and Southbound buffered bike lanes from just south of McKenzie Ave to Torquay Dr;
- Replacement of underground utility infrastructure (water, sewer, storm drainage);
- Replacement of utility service lines (from utility main to property line);
- Traffic signal additions or upgrades;
- Shelbourne St/Blair Ave signal upgrade from pedestrian activated signal to full traffic signal;
- New full signal at intersection of Cedar Hill Rd and Feltham Rd;
- New full signal at intersection of Shelbourne St and Torquay Dr;
- Rehabilitation and visibility upgrades for other signals;
- Full repaving of roadway including upgrade of any existing areas of weak road base;
- New highly visible reflective road markings and embedded pavement reflectors;
- Sidewalk repairs and upgrades;
- Reduced intersection crossing distances for pedestrians;
- Improved roadway lighting;
- New street trees and landscaping, where space permits;
- Improved bus stops with new shelters and lighting;
- New street furniture – bike locking posts, waste receptacles, benches.